ACTION FOR AGRICULTURAL RENEWAL IN MAHARASHTRA
Raisoni Park, Building No. 2/23, A-B, Market Yard, Pune - 411 037.
020-24264641, 24266303. admin@afarm.org www.afarm.org
Golden Jubilee Journey (1969-2019) An Association of Voluntary Organizations engaged in Water, Agriculture & Livelihoods Development

निविदा दस्तऐवज

निविदा क्रमांक: अफार्म/ निविदा / ७ / २०२६-२७

मृद व जलसंधारण कामासाठी कंत्राटदारांची निवड करणे

निविदा आमंत्रण करणारी संस्था

अॅक्शन फॉर अॅग्रिकल्चरल रिन्युअल इन महाराष्ट्र (अफार्म)
रायसोनी पार्क, मार्केट यार्ड, पुणे, महाराष्ट्र -४११०३७

- Society Registration No. : MH/135/Ahmednagar, Dt. 28/10/1969
- Trust Registration No. : F-5319, Date 18/11/1969
- FCRA Registration No. : 083930013, dated 14/01/1985
- NITI Aayog Registration No. : MH/2016/0099114
- CSR Registration No. : CSR00000092
- Income Tax Registration No. (12A) : AAATA3756FE20210 (Up to AY 2026-27)
- Income Tax (80G)Registration No. : AAATA3756FE20218 (Up to AY 2026-27)
- Permanent Account No. : AAATA3756F

मृद व जलसंधारण कामासाठी कंत्राटदार नेमणे

(निविदा – अफार्म/ ७ /२०२६-२७)

निविदा सादर करण्यासाठी सूचना

१) पुणे, सातारा, अहिल्यानगर, नाशिक, धुळे, नंदुरबार, धाराशिव, यवतमाळ, लातूर व वलसाड (गुजरात) जिल्ह्यांतील निवडक गावामध्ये मृद व जलसंधारण कामासाठी सीसीटी, वॅट, फार्म बंडिंग, लूज बोल्डर स्ट्रक्चर, गॅबियन स्ट्रक्चर, रिचार्ज पीट, शेत तळे, माती नाला बांध व जुन्या व नवीन सिमेंट चेक डॅम बांधकाम करणे, जुन्या तलावातील गाळ काढणे इ. कामांसाठी नोंदणीकृत व अनुभवी कंत्राटदार, पोकलॅन/जेसिबी मशिनधारक व बांधकाम साहित्य पुरवठादाराची निवड करावयाची आहे. सदर निवड ऑक्टोबर २०२६ ते सप्टेंबर २०२७ या कालावधी करिता करण्यात येईल.

२) विस्तृत निविदा फॉर्म अफार्मच्या संकेतस्थळावर www.afarm.org/proposals उपलब्ध आहे.

३) निविदा फॉर्म नुसार **तांत्रिक प्रस्तावाचा भाग** म्हणून खालील कागदपत्रे सादर करणे आवश्यक आहे.

- **प्रपत्र १** - कंत्राटदार यांचा पूर्वानुभव - मृद व जलसंधारण कामांचा किमान ३ वर्षांचा अनुभव आवश्यक आहे. सोबत work order नुसार पुरवठा वेळेत पूर्ण केल्याचे संस्थात्मक ग्राहकाचे पूर्णत्व प्रमाणपत्र जोडावे. अन्यथा जेथे पूर्णत्व प्रमाणपत्र नसेल, अशा बाबतीत वर्क ऑर्डरची प्रत जोडावी.
- **प्रपत्र २** - मृद व जलसंधारणच्या तत्सम कामांची मागील तीन वर्षांची सरासरी वार्षिक उलाढाल किमान रु.१ कोटी आवश्यक आहे. सीए (C.A.) यांचे आर्थिक उलाढाल प्रमाणपत्र आवश्यक.
- **प्रपत्र ३** – कंत्राटदाराच्या मालकीच्या यंत्र सामुग्रीचा तपशिल.
- कंत्राटदार यांचे नोंदणी प्रमाणपत्र.
- पॅन कार्ड.
- गेल्या ३ वर्षांचे आयकर रिटर्न.
- वस्तू आणि सेवा कर (GST) नोंदणी प्रमाणपत्र.
- गेल्या तिमाहीचे वस्तू आणि सेवा कर (GST) रिटर्नस - GSTR 3B
- तीन प्रमुख संस्थात्मक ग्राहक (Institution Buyers) माहिती (नाव, संपर्क क्र. इ.)
- **प्रपत्र ४ -** प्रतिज्ञापत्र.

४) **आर्थिक प्रस्ताव** निविदांमध्ये जोडलेल्या विहित नमुन्यात आर्थिक प्रस्ताव सादर करणे आवश्यक आहे. त्यासाठी साहित्य / वस्तू च्या तपशील व प्रकारानुसार पुरवठादारांनी दर देणे अपेक्षित आहे.

५) आर्थिक प्रस्तावात नमूद केलेले दर जीएसटीसह आहेत की नाही हे स्पष्टपणे नमूद करावे. दिलेल्या दरांसाठी जीएसटी टक्केवारी आणि एचएसएन कोड निर्दिष्ट करावा.

६) कंत्राटदार यांनी त्यांचा संपूर्ण प्रस्ताव (तांत्रिक + आर्थिक) सर्व कागदपत्रांसह हार्ड कॉपीमध्ये त्यांच्या आस्थापनेच्या लेटरहेडवर निर्दिष्ट नमुन्यात अंतिम तारखेपर्यंत अफार्म मुख्यालय, रायसोनी पार्क, बिल्डिंग नंबर-२, अ-ब, मार्केटयार्ड, पुणे-३७ येथे अथवा sandipgade@afarm.org वर ईमेलद्वारे सादर करावा.

७) सादर केलेल्या प्रत्येक कागदपत्रावर कंत्राटदार यांचे अधिकृत प्रतिनिधीची स्वाक्षरी आणि शिक्का असला पाहिजे.

८) निविदेतील कंत्राटदार यांनी दिलेले दर हे दिनांक १ ऑक्टोबर २०२६ ते ३० सप्टेंबर २०२७ या कालावधीसाठी लागू राहतील.

९) प्रस्ताव सादर करण्याची अंतिम तारीख आणि वेळ: दिनांक २८ सप्टेंबर २०२६, संध्याकाळी ५.३० पर्यत.

१०) कंत्राटदार यांच्या काही विशिष्ट अटी आणि शर्ती असल्यास, त्या आर्थिक प्रस्तावाच्या शेवटी नमूद केल्या पाहिजेत.

११) प्राप्त निविदांची निकषानुसार छाननी करून पात्र कंत्राटदार यांची अफार्म स्तरावर निवडसूची तयार केली जाईल. केवळ निवडसूचित समाविष्ट झालेल्या पुरवठादारांशी पुढील कार्यवाहीबाबत संपर्क साधला जाईल.

१२) कोणतेही कारण न देता निविदा पूर्णत:/अंशत: नाकारण्याचे अधिकार संस्था अबाधित ठेवत आहे.

१३) अधिक माहितीसाठी ९४२१५६९०९८, ०२०-२४२६६३०३ येथे संपर्क साधावा.

कार्यकारी संचालक
अफार्म, पुणे

(सदर प्रपत्र कंपनीच्या लेटरहेडवर घ्यावे)

तांत्रिक प्रस्ताव : प्रपत्र - १

तारीख:

कंत्राटदार यांचा पूर्वानुभव

हे प्रमाणित करण्यात येते की आमच्या कंपनीने खालीलप्रमाणे निविदा सादर करण्याच्या तारखेपर्यंत अशा प्रकारची कामे पूर्ण केली आहेत.

वर्ष	ग्राहकाचे नाव, पत्ता व संपर्क नंबर सह	केलेल्या कामाचे नाव	केलेल्या कामाचे परिमाण (Quantity)	वर्क ऑर्डर क्रमांक आणि तारीख	केलेल्या कामाचे मूल्य रु.	काम पूर्ण झाल्याची तारीख
२०२५-२६						
२०२४-२५						
२०२३-२४						

अधिकृत प्रतिनिधी सही

नाव आणि शिक्का

(सदर प्रपत्र चार्टर्ड अकाउंटंट यांच्या लेटरहेडवर घ्यावे)

तांत्रिक प्रस्ताव : प्रपत्र – २ (अ)

चार्टर्ड अकाउंटंट यांनी जारी केलेले एकूण आर्थिक उलाढाल प्रमाणपत्र

(TO WHOMSOEVER IT MAY CONCERN)

हे प्रमाणित करण्यात येते की, (कंत्राटदार यांचे नाव) यांचे नोंदणीकृत कार्यालय/दुकान (तपशीलवार कार्यालयीन पत्ता देणे) या ठिकाणी आहे. लेखापरीक्षित आर्थिक विवरणपत्रावर आधारित खालील प्रमाणे वर्ष निहाय आर्थिक उलाढाल आहे.

अ. क्र.	आर्थिक वर्ष	उलाढाल (रु. लाख)
१)	२०२३-२४	
२)	२०२४-२५	
३)	२०२५-२६	
	एकूण रू	

वरील माहिती/आकडे माझ्या माहितीनुसार आणि विश्वासानुसार खरे आणि अचूक आहेत. मला/आम्हाला/ याची चांगली जाणीव आहे की कोणतीही खोटी माहिती/बनावट कागदपत्रे सादर केल्याने निविदा नाकारली जाईल किंवा कोणत्याही टप्प्यावर योग्य कायद्यानुसार खटला चालवला जाईल.

चार्टर्ड अकाउंटंटची स्वाक्षरी

फर्मचे नाव:

नोंदणी क्रमांक:

तारीख:

ठिकाण:

(चार्टर्ड अकाउंटंटचा शिक्का)

ईमेल आयडी:

UDIN:

टीप:

१. UDIN शिवाय उलाढाल प्रमाणपत्र नाकारले जाईल.

२. लेखापरीक्षण न केलेल्या आर्थिक विवरणपत्रातील उलाढाल विचारात घेतली जाणार नाही.

३. द इन्स्टिट्यूट ऑफ चार्टर्ड अकाउंटंट्स ऑफ इंडियाच्या वेबसाइटवर उपलब्ध असलेल्या UDIN दस्तऐवजात नमूद केलेले उलाढाल आणि हे प्रमाणपत्र समान असले पाहिजे. अशा परिस्थितीत काही फरक असल्यास इन्स्टिट्यूट ऑफ चार्टर्ड अकाउंटंट्स ऑफ इंडियाच्या वेबसाइटवर उपलब्ध असलेल्या उलाढालीचा विचार केला जाईल.

(सदर प्रपत्र चार्टर्ड अकाउंटंट यांच्या लेटरहेडवर घ्यावे)

तांत्रिक प्रस्ताव : प्रपत्र – २ (ब)

चार्टर्ड अकाउंटंट यांनी जारी केलेले मृदा- जलसंधारण कामांचे उलाढाल प्रमाणपत्र

(TO WHOMSOEVER IT MAY CONCERN)

हे प्रमाणित करण्यात येते की, (कंत्राटदार यांचे नाव) यांचे नोंदणीकृत कार्यालय/दुकान (तपशीलवार कार्यालयीन पत्ता देणे) या ठिकाणी आहे. लेखापरीक्षित आर्थिक विवरणपत्रावर आधारित खालील प्रमाणे वर्ष निहाय आर्थिक उलाढाल आहे.

अ. क्र.	आर्थिक वर्ष	उलाढाल (रु. लाख)
१)	२०२३-२४	
२)	२०२४-२५	
३)	२०२५-२६	
	एकूण रू	

वरील माहिती/आकडे माझ्या माहितीनुसार आणि विश्वासानुसार खरे आणि अचूक आहेत. मला/आम्हाला/ याची चांगली जाणीव आहे की कोणतीही खोटी माहिती/बनावट कागदपत्रे सादर केल्याने निविदा नाकारली जाईल किंवा कोणत्याही टप्प्यावर योग्य कायद्यानुसार खटला चालवला जाईल.

चार्टर्ड अकाउंटंटची स्वाक्षरी

फर्मचे नाव:

नोंदणी क्रमांक:

तारीख:

ठिकाण:

(चार्टर्ड अकाउंटंटचा शिक्का)

ईमेल आयडी:

UDIN:

टीप:

१. UDIN शिवाय उलाढाल प्रमाणपत्र नाकारले जाईल.

२. लेखापरीक्षण न केलेल्या आर्थिक विवरणपत्रातील उलाढाल विचारात घेतली जाणार नाही.

३. द इन्स्टिट्यूट ऑफ चार्टर्ड अकाउंटंट्स ऑफ इंडियाच्या वेबसाइटवर उपलब्ध असलेल्या UDIN दस्तऐवजात नमूद केलेले उलाढाल आणि हे प्रमाणपत्र समान असले पाहिजे. अशा परिस्थितीत काही फरक असल्यास इन्स्टिट्यूट ऑफ चार्टर्ड अकाउंटंट्स ऑफ इंडियाच्या वेबसाइटवर उपलब्ध असलेल्या उलाढालीचा विचार केला जाईल.

(सदर प्रपत्र कंपनीच्या लेटरहेडवर घ्यावे)

प्रपत्र – ३ कंत्राटदाराच्या मालकीच्या यंत्र सामुग्रीचा तपशिल

तारीख:

अनु.क्र.	यंत्र सामुग्रीचे नाव	तांत्रिक तपशिल	एकूण संख्या	खरेदी वर्ष

अधिकृत प्रतिनिधी सही

नाव आणि शिक्का

(सदर प्रपत्र कंपनीच्या लेटर हेडवर घ्यावा)

आर्थिक प्रस्ताव प्रपत्र

प्रती,
कार्यकारी संचालक,
अफार्म - पुणे.

विषय: **मृद व जलसंधारण कामे करण्यासाठी आर्थिक प्रस्ताव सादर करणे.**
संदर्भ: ---------- रोजी ---------- वृत्तपत्रातील जाहिरात.

महोदय,

वरील विषयानुसार, आम्ही आमचा आर्थिक प्रस्ताव सादर करत आहोत ज्यामध्ये बाब निहाय कामांच्या दराचा समावेश आहे.

No	Item Description	UoM	Proposed unit rate (Completed item)
A	**Site cleaning**		
1	Cleaning grass, bushes, shrubs, saplings and trees girth, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used etc. complete by mechanical / manual means	Sqm	
B	**Excavation by Machine (for Desilting, Foundation, CB, FB, DCCT & Recharge Pit, Farm Pond etc)**		
1	Excavation in all kinds **of soils** including boulders up to 0.6 m diameter (0.113 cum) for canal, seating of embankment, filter drains / catch water drains etc., and placing the excavated stuff neatly in dump area etc. complete with transportation upto 15 m and all lifts as directed.	Cum	
2	Excavation in all kinds of **Soft murum** including boulders up to 0.6 m diameter (0.113 cum) for canal, seating of embankment, filter drains / catch water drains etc., and placing the excavated stuff neatly in dump area etc. complete with transportation up to 15 m and all lifts as directed.	Cum	
a	For 16 to 250 m transportation – one way	Cum	
b	For 251 to 500 m transportation – one way	Cum	
3	Excavation in **hard murum** including boulders up to 0.6 m diameter (0.113 cum) for canal, seating of embankment, filter drains / catch water drains etc., and placing the excavated stuff neatly in dump area etc., complete with transportation up to 15m and all lifts as directed.	Cum	
a	For 16 to 250 m transportation – one way	Cum	
b	For 251 to 500 m transportation – one way	Cum	
4	Refilling in foundations/buffer filling without transportation of excavated soil, sand and murum without compaction etc. complete	Cum	
5	**Guide Bund-**Formation, levelling, compaction, dressing with proper size & shape of guide bund with excavated material at minimum 1m apart from edge of nalla. (Rate applicable during ongoing work of de-silting of CNB / ENB as applicable)	Cum	
6	Machine shifting charges (Applicable for Farm pond & Recharge Pit work only)		

No	Item Description	UoM	Proposed unit rate (Completed item)
a	Up to 500 m	Mtr	
b	Next every additional 100 m	Mtr	
C	**Excavation Work by Machine for Construction of New Earthen Nala Bund/ Minor/Large Tank**		
1	Providing **cut off trench** filling using selected impervious soil **from approved borrow areas including cost of all** materials, machinery, labour, all other operations such as collection of soil, spreading soil in layer of specified thickness, sorting out, breaking clods, levelling, sectioning edges / sides, watering, compacting each layer to density control of not less than 95 percent or as stipulated using vibratory compactor including cost of water etc. complete with transportation up to1 km and all lifts as directed	Cum	
2	Providing **hearting embankment** using selected impervious soil from approved borrow areas in layers including cost of all materials, machinery, labour, all other operations such as collection of soil, spreading soil in layer of specified thickness, sorting out, breaking clods, levelling, sectioning edges / sides, watering, compacting each layer to density control of not less than 95 percent or as stipulated using vibratory compactor including cost of water etc., complete with transportation up to1 km and all lifts as directed.	Cum	
3	Providing **casing embankment** using selected pervious material available directly from excavation in layers including cost of all materials, machinery, labour, all other operations such as collection of material, spreading material in layer of specified thickness, sorting out, breaking clods, leveling, sectioning edges / sides, watering, compacting each layer to density control of not less than 95 percent or as stipulated using vibratory compactor including cost of water etc. complete with transportation up to1 km and all lifts as directed	Cum	
4	Providing and constructing 250-300 mm thick **dry rubble stone pitching** with pin headers at 2 per sqm using stones and stone chips from **approved source** including cost of all materials, labour, hand packing / wedging stone chips, finishing etc., complete with transportation up to 1 km and all lifts as directed.	Sqm	
a	Additional transportation Charges 1-2 Km	Km	
b	Additional transportation Charges 2-3 Km	Km	
D	**Construction of Stone Masonry Nala Bund / Building**		
1	Providing and laying in situ cement concrete of grade M-10 (20 MSA) (Cement 4.4 bags/Cum) of trap / granite / quartzite / graded metal for foundation and bedding with Concrete Mixer including placing, compacting, curing etc. complete with all transportations & lifts as directed	Cum	
2	Dismantling the Stone Masonry in cement mortar in case repairing work including stacking the material with all lifts etc. complete as directed	Cum	
3	Providing U.C.R. masonry in C.M. 1:5 in foundation / sub structure with lift up to 1.5 m. including striking joints, curing etc. complete as directed.		
a	For water retaining structures (45% mortar).	Cum	
4	Providing U.C.R. masonry in C.M. 1:5 in superstructure with lift up to 1.5 m. including striking joints, curing etc. complete as directed.	Cum	
a	For water retaining structures (45% mortar)	Cum	
5	Providing first class Burnt Brick masonry with conventional/I.S. type bricks in cement mortar 1:6 in super structure including striking joints, raking out joints, watering and scaffolding etc. Complete	Cum	
6	Providing internal cement plaster 12mm thick in single coat in cement mortar 1:3 without neeru finish to concrete, Brick or stone surface, in all positions including scaffolding and curing complete as directed	Sqm	
7	Providing external cement plaster 20mm thick in two coats in cement mortar 1:5 to concrete, UCR & brick surface in all positions including scaffolding and curing complete as directed	Sqm	
8	Providing grooved pointing with cement mortar 1:3 for UCR work including scaffolding and curing etc. complete as directed	Sqm	

No	Item Description	UoM	Proposed unit rate (Completed item)
9	Providing rubble Soling using 230mm size rubble including filling voids with murrum ramming, watering complete as directed by site in charge	Cum	
10	Dewatering by pumping out water collected with 5 to 10 HP pumps including cost of all materials, machinery, labour, providing sump and all other ancillary operations whenever necessary etc. complete under specific and indispensable circumstances with prior approval from competent authority with authentic evidence of records justifying dewatering etc. complete as directed.	BHP/Hr	
E	**Loose Boulder Structure/Gabion Structures**		
1	Collection & Carting of stones from 100 m distance and Construction of Loose boulder structures for foundation & superstructure with locally available stone (dry boulders)	Cum	
2	Providing and fixing G. I. wire mesh for gabion structure; wire mesh made form 4 mm galvanized steel wire @ 32kg per 10 sq. m having minimum tensile strength of 300Mpa confirming to IS: 280 and galvanizing coating confirming to IS: 4826 woven into mesh with double twist, mesh size not exceeding 100 x 100 mm, all loose ends to be tied with 4mm galvanized steel wire etc. complete under tidal conditions.	Sqm	
3	Providing and construction of a gabion structure filled with hand packed stones of 20 to 50 kilogram in weight or boulders with least dimension of 200 mm; so as to give total mass required with transportations up to 1km and all lifts including fusing top of gabions, tying to each other and laying to required line, level, slope as per drawing, section as directed and etc. complete under tidal conditions.	Cum	
F	**Cement Concreting Work**		
1	Providing and casting in situ RCC M-10 (4.5 bag cement @ 53 grade cement/ cubic meter of concrete) of trap / granite / quartzite / gneiss metal including centring, formwork, compacting, roughening them if required complete, with fully automatic microprocessor-based PLC with SCADA enabled reversible Drum Type mixer with crush sand	Cum	
2	Providing and casting in situ RCC M-15 (6 bag cement @ Rs. 53 grade cement /cubic meter of concrete) of trap / granite / quartzite / gneiss metal including cantering, formwork, compacting, roughening them if special finishing if required complete, with fully automatic microprocessor-based PLC with SCADA enabled reversible Drum Type mixer with crush sand	Cum	
3	Providing and casting in situ RCC M-20 (with 8 bag cement @ 53 grade cement/cubic meter of concrete,) of trap / granite / quartzite / gneiss metal including cantering, formwork, compacting, roughening them if special finishing if required complete, with fully automatic microprocessor-based PLC with SCADA enabled reversible Drum Type mixer with crush sand	Cum	
4	Providing and laying in situ M-15 cement concrete of trap / granite / quartzite / gneiss metal with 40% plum of trap stones for foundation and bedding of retaining walls etc. including necessary formwork, compacting, curing, bailing out water manually in tidal range etc. complete.	Cum	
G	**Pipe Work**		
1	Providing and laying cement concrete pipe of IS 458:2003 NP-2 class of 300mm diameter and 2 m long with collar in proper line, level and slope including necessary excavation, back-filling, removal of all loose material & debris from inlet & outlet side area of R. C. C. pipe etc. complete.	No	
2	Providing and laying cement concrete pipe of IS 458:2003 NP-2 class of 450mm diameter and 2.5 m long with collar in proper line, level and slope including necessary excavation, backfilling, removal of all loose material & debris from inlet & outlet side area of R. C. C. pipe etc. complete.	No	
3	Providing and laying cement concrete pipe of IS 458:2003 NP-2 class of 600mm diameter and 2.5 m long with collar in proper line, level and slope including necessary excavation, backfilling, removal of all loose material & debris from inlet & outlet side area of R. C. C. pipe etc. complete.	No	

No	Item Description	UoM	Proposed unit rate (Completed item)
4	Providing and laying cement concrete pipe of IS 458:2003 NP-2 class of 900mm diameter and 2.5 m long with collar in proper line, level and slope including necessary excavation, backfilling, removal of all loose material & debris from inlet & outlet side area of R. C. C. pipe etc. complete.	No	
H	**Recharge Shaft**		
1	Cutting of ramp for drilling vehicles movement in the NDW site	cum	
2	Backfilling of ramp for drilling vehicles movement in the NDW site	cum	
3	Drilling Bore (165 mm)	m	
4	Providing & Fixing Perforated PVC Casing Pipe (Dia.180mm, 6 kg/ cm. sq. pressure including transportation.	m	
5	End Cap (Dia.180 mm) for PVC casing pipe	No	
6	Providing ISI standard R.C.C Ring- 900 mm dia, Length 0.30 m & 50 mm thickness Class-NP-II	No	
7	Providing and casting Pre cast RCC M-10 for 900mm dia. RCC pipe END CAP	No	
8	Providing & filling of (60 mm) Gravels outside of ring in the Recharge Pit	cum	
9	Providing & Filling of (60 mm) Gravels inside of RCC Ring in the Recharge Pit and 0.30 m above Pit.	cum	

मी/आम्ही याद्वारे घोषित करतो की प्रदान केलेली माहिती खरी आणि बरोबर आहे आणि मी/आम्ही निविदेत नमूद केलेल्या सर्व अटी आणि शर्तींशी सहमत आहे.

कंत्राटदाराचे नाव:

स्वाक्षरी:

तारीख:

(सदर प्रपत्र कंपनीच्या लेटर हेडवर घ्यावा)

तांत्रिक प्रस्ताव : प्रपत्र – ४

प्रतिज्ञापत्र

कंत्राटदाराचे नाव:

निविदा जाहिरात तारीख:

मी……वय…… पत्ता……..……..
(अधिकृत स्वाक्षरीकर्ता), याद्वारे, या शपथपत्राद्वारे, सत्यतेने सादर करतो की, मी .....या आस्थापनेचा मालक असून मी कागद पत्राची छाननी करण्यासाठी कागदपत्रे सादर करत आहे व खाली नमूद केलेल्या अटींशी सहमत आहे.

१. मी, मृद व जलसंधारण कामे करण्यासाठी sandipgade@afarm.org या ईमेलवर किंवा AFARM मुख्यालय रायसोनी पार्क बिल्डींग नंबर २, अ- ब मार्केट यार्ड पुणे येथे निविदा सादर केली आहे.

२. मी निविदा दस्तऐवजात समाविष्ट असलेल्या सर्व अटी आणि शर्ती, तपशील काळजीपूर्वक वाचले आहेत, पूर्णपणे अभ्यासले आहेत आणि समजून घेतले आहेत. मी याद्वारे या सर्व अटी स्वीकारतो. मी निविदा दस्तऐवजातील अटी आणि शर्तींचे पालन करण्यास सहमत आहे आणि निविदा दस्तऐवजात नमूद केलेल्या अटी आणि शर्ती, तपशीलांनुसार काम करण्यास सहमत आहे.

३. मी याद्वारे शपथ घेऊन जाहीर करतो की या निविदेचे दस्तऐवज खरे, बरोबर आणि अचूक आहेत. सादर केलेल्या कागदपत्रांमध्ये कोणत्याही चुका आणि त्रुटी नाहीत.

४. सादर केलेल्या कोणत्याही खोट्या/फसव्या कागदपत्रे/माहिती सादर केल्याबद्दल मी भारतीय दंड संहिता अंतर्गत कारवाईस जबाबदार आहे.

५. सादर केलेल्या निविदेतील दरामध्ये काम करण्यास बांधील असून ठरलेल्या कालावधीत काम पूर्ण करून देईन यामध्ये फसवणूक केल्यास मी भारतीय दंड संहिता अंतर्गत कारवाईस जबाबदार आहे.

६. मी/आम्ही …….. याद्वारे गंभीरपणे सहमत आहे की, मी/आम्ही मृद व जलसंधारण कामे करण्यासाठी स्वेच्छेने प्रतिज्ञापत्र दिले आहे.

म्हणून हे प्रतिज्ञापत्र.

स्थान :

तारीख:

कंत्राटदाराची स्वाक्षरी व शिक्का